CHALO INTERIORS

Timeless Form

Version : 2026 Edition
SKU : LR-TU-004
Location: Mumbai , Navi Mumbai, Thane & Pune
TV Unit Size: 7'X15"
Scope of work: TV Unit
BOQ(Bill of Quantities)

Sr. No.		Work Item	Scope of Work / Specification	Area / Qty.	Unit	Cost
			TV Unit			
CARPENTRY WORK	1		**CARPENTRY WORK**			
		TV Unit - PU Finish	Accent TV Wall Unit wall-Supply, fabrication, and installation of a custom TV unit as per approved design usingHDHMR (as specified), finished with PU Finish. Scope includes shelves, edge banding, hardware, installation, and all labour, materials, and accessories required for a complete finished unit.	8	sq.ft	₹116,080
		TV Unit Back Wall Design- POP Punning with Groove Line	Providing and applying POP punning to wall surfaces with decorative groove line detailing, including surface preparation, levelling, smooth finishing, and installation as per approved design	14	r.ft	
		TV Unit Back Wall Design- POP Punning with Design	Providing and applying POP punning to wall surfaces with decorative design detailing, including surface preparation, levelling, smooth finishing, and installation as per approved design	39	r.ft	
		TV Unit Back Wall design- Ply & Laminated Finish	BWR Grade Plywood Fabrication, and installation of a custom Bed back Panelling as per approved design	54	sq.ft	
ELECTRICAL WORK & FIXTURES	2		**ELECTRICAL WORK & FIXTURES**			
		TV Cable	TV point shifting charges	1	nos	₹19,150
		Telephone Cable	Supply and installation of Cat 6 cable for telephone/data points, including concealed laying and termination.	1	nos	
		Internet/network connections	Supply and installation of Cat 6 cable for internet/network points, including concealed laying and termination.	1	nos	
		Hidden Switch board for TV (Location behind TV), Components	2 module board (1 sockets) Supply of concealed TV switch board with socket, modular plate, mounting box. (Brand: Anchor by Panasonic – Roma)	-	-	
			6A Socket	1	nos	
			2 Module Plates	1	nos	
			2 Module Boxes	1	nos	
		Switch board for TV unit	8 module board (2 sockets & 4 switches) (Brand: Havells / GM Modular / Goldmedal, or equivalent approved brand) Supply of concealed TV switch board with sockets, modular plate, mounting box, and approved brand accessories, as per approved design.		-	
			6A switches	2	nos	
			6A sockets	2	nos	
			8 Module Plate	1	nos	
			8 Mounting boxes	1	nos	
		Electrical Work - Labour	Electrical Work : Supply and installation of concealed black PVC electrical conduits, copper wiring, concealed electrical boxes, junction boxes, and all necessary accessories, including labour for conduit laying, wire pulling, connections, testing, and commissioning to ensure all electrical points are complete and fully functional. Exclusions: Modular switches, sockets, light fixtures, fans, and electrical appliances unless otherwise specified..	5	nos	
		Decorative light fixture	Supply of Decorative wall light fixtures (as per Design)	2	nos	
		Profile light fixture	Supply of Decorative Profile light fixture (as per Design)- rate per 5M.	1	nos	
		Profile light patti fixture	Supply of Decorative Profile light outer Patti (as per Design)	7	r.ft	
		Profile Light Driver	Providing and installing suitable LED profile light driver, including wiring, connections, testing, and installation as per site requirements. (One per 10ft)	1	nos	

Note: You can choose the items you wish to include and design your TV Unit according to your design preferences and budget.

Contact us.

Visit Website

Note: Final pricing may vary based on site conditions, measurements, project location, material selections, and specific project requirements. The final cost will be confirmed after the site visit and detailed discussion.