CHALO INTERIORS

Minimal Warmth

Version : 2026 Edition
SKU No.: BR-BA-002
Location: Mumbai , Navi Mumbai, Thane & Pune
Bedroom Size: 12'X10'
Scope of work: Complete Bedroom Renovation
BOQ(Bill of Quantities)

Sr. No.		Work Item	Scope of Work / Specification	Area / Qty.	Unit	Cost
Bedroom (Size: 12'X10')						
FALSE CEILING WORK	2.1	**FALSE CEILING WORK**				
		False Ceiling Work (1 layer)	(False ceiling Size: 12'X10') Supply and installation a 1-layer false ceiling using gypsum board, including GI framework, finishing and surface preparation as per approved design.	120	sq.ft.	₹11,100
		LED light Fittings Cutout (Labour)	Scope includes provision of cut-outs for spotlights, LED panels, and all necessary LED lighting fixtures, and accessories as per the approved design.	6	nos	
CARPENTRY WORK	2.2	**CARPENTRY WORK**				
		Bed with Side Cushioning & Hydraulic Storage	BWR Grade Plywood, (Bed Size: 6'x5'6") Supply and installation of a custom-designed bed with hydraulic storage as per the approved design, manufactured using high-quality plywood with fabric finish. Including heavy-duty hydraulic lift mechanism, all necessary hardware, edge finishing, labour, transportation, installation, and finishing, complete and ready for use.	1	nos	₹138,810
		Bed Headboard with Laminate finish	Providing and fixing a bed headboard with plywood framework, finished with selected laminate, including edge finishing, necessary hardware, and installation as per approved design and site requirements.	21	sq.ft	
		Bed Back Wall Design- POP Punning with Groove Line	Providing and applying POP punning to wall surfaces with decorative groove line detailing, including surface preparation, levelling, smooth finishing, and installation as per approved design	48	r.ft	
		Decorative Cushions	Providing and supplying decorative cushions with quality filling and selected fabric/upholstery, including stitching and finishing as per approved design.	2	nos	
		Bedsheet	Providing premium-quality bed sheet in selected fabric, size and design as per approved selection.	1	nos	
		Tables with laminate Finish (2 Drawer)	BWR Grade Plywood, Side Table (Size: 1'6'x.1'2" with 2 drawer each): Supply and installation of SideTable in plywood with laminate finish, including all materials and labour, necessary framing, fixing hardware, polishing/finishing, and all accessories required for a complete and finished installation.	2	nos	
ELECTRICAL WORK & FIXTURES	2.3	**ELECTRICAL WORK & FIXTURES**				
		Electrical Work - Labour	Electrical Work : Supply and installation of concealed black PVC electrical conduits, copper wiring, concealed electrical boxes, junction boxes, and all necessary accessories, including labour for conduit laying, wire pulling, connections, testing, and commissioning to ensure all electrical points are complete and fully functional.Exclusions: Modular switches, sockets, light fixtures, fans, and electrical appliances unless otherwise specified..	10	nos	₹19,840
		Spot Light	Supply of Decorative Spot light fixtures (as per Design)	4	nos	
		Profile light fixture	Supply of Decorative Profile light fixture (as per Design)- rate per 5M.	1	nos	
		Profile light patti fixture	Supply of Decorative Profile light outer Patti (as per Design)	7	r.ft	
		Ceiling concealed LED lights fixture	Supply of LED Panel fixtures (as per Design) brand : Havells 6-Watt LED Panel Light	6	nos	
		Fan	Providing and installing ceiling fan as per design including necessary wiring for fitting.	1	nos	
PAINTING WORK	2.4	**PAINTING WORK**				
		ete Bedroom Interior Painting (Walls & False ceiling)	Surface preparation, putty application, primer, sanding, and application of two coats of premium interior emulsion paint to all interior walls and balcony walls (where applicable), including all labour, materials, tools, and consumables required to achieve a smooth, uniform, and finished surface.	426	Sq.ft.	₹17,892
ACCESSORY ITEMS	2.5	**ACCESSORY ITEMS**				
		Solid Curtains	800rs. /r.m. Providing and installing plain solid-color curtains as per approved design and site measurements.	12	r.m.	₹19,200
		Semi-Sheer/Light-Filtering Curtains	600rs. /r.m. Providing and installing sheer curtains as per approved design and site measurements.	12	r.m.	
		Curtain Rods & Fitting	Supply of stainless steel curtain rod complete with accessories.(Hidden in false ceiling)	24	r.ft.	

Note: You can choose the items you wish to include and design your bedroom according to your design preferences and budget.

Contact us.

Note: Final pricing may vary based on site conditions, measurements, project location, material selections, and specific project requirements. The final cost will be confirmed after the site visit and detailed discussion.